# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/OW/WORK_INDENT9308/CALL-2

## APPROVED SCHEDULE - B

**Tender Notification No: No.EE/BTP/BBMP/E-PMT/16/2013-14, Date: 06.12.2013**

**Estimate for the Re-construction of SWD drains in Byatarayanapura Village in Ward no. 07.**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of C T SOMASHEKAR | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 132.3 | KSRRB M200-15.1: Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 meters complete as per specifications. Iii) dismantling stone masonry, a rubble stone masonry in lime mortar, Rubble stone masonry in cement mortar. ) Page No. 148/ item No. 18.27 / PWD SR 2013-14 | cum | 198.87 | Rupees One Hundred Ninety Eight and Eighty Seven Paise Only |
| 2 | 138.92 | KSRB 2-2.1 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (P. 5, I.No. 2.3) SR-2013-14 | cum | 150.22 | Rupees One Hundred Fifty and Twenty Two Paise Only |
| 3 | 46.31 | KSRB 4-1.2: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P. 12, I.No. 4.2) SR-2013-14 | cum | 4452.15 | Rupees Four Thousand Four Hundred Fifty Two and Fifteen Paise Only |
| 4 | 158.76 | KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (P. 25, I.No. 5.6) SR-2013-14 | cum | 3514.46 | Rupees Three Thousand Five Hundred Fourteen and Forty Six Paise Only |
| 5 | 23.15 | Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-320Kg/cum) ( P. 19, I.No. 4.49.1) SR-2013-14 | cum | 6403.44 | Rupees Six Thousand Four Hundred Three and Forty Four Paise Only |

Executive Engineer
Byatarayanapura Divn.
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

| | | | | | |
|---|---|---|---|---|---|
| 6 | 176.4 | KSRB 15.1.3 – do – Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.122.I.No. 15.3) SR-2013-14 | sqm | 79.12 | Rupees Seventy Nine and Twelve Paise Only |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92